


ADDENDUM No. 1

TIPPECANOE COUNTY BRIDGE No 165

May 11, 2016

INDEX OF CONTENTS

Addendum No. 1 consists of 3 pages
and one 6 page attachment



Stewart W. Kline
P.E. No. 870144

H. STEWART KLINE & ASSOCIATES, INC.
106 South 16th Street
Lafayette, IN 47902
www.HSKline.com

Addendum No. 1

2016 TIPPECANOE COUNTY BRIDGE No 165

TO: ALL BIDDERS

Addendum No. 1, dated May 11, 2016, to the Plans and Specifications for the above noted project as prepared by H. Stewart Kline & Associates, Inc.

This Addendum shall hereby be made a part of the Contract Documents, the same as if originally bound thereto. The following clarifications, amendments, additions, revisions, changes, and/or modifications, change the original Contract Documents only in the manner and to the extent hereinafter specified in the Addendum.

Each Bidder shall acknowledge receipt of the Addendum on his proposal. All bidders should review these items to ascertain whether their Work is affected by the same.

SUBGRADE TREATMENT:

Wherever shown in the plans Subgrade Treatment Type IA is shown it shall be changed to Type IC, and wherever Type IIIA is shown it shall be changed to Type II.

PEDESTRIAN RAILING:

Post spacing on pedestrian railings shall not exceed 5'-0".

As shown on plan sheet 10, spindles shall be omitted at the eastern stair from the base up 22 treads in order to minimize debris build up.

The railing system shall conform to the requirements of the current Indiana Building Code. The railing system shall be demonstrated by computation to be capable of withstanding the following structural loads without exceeding the permitted design working stress limits for railing systems, anchors, and connections. Each load shall be applied to produce the maximum stress in each of the respective components.

Top rails shall be capable of withstanding: 1) A concentrated load of 200 pounds applied at any point in any direction; and, 2) A uniform load of 50 pounds per linear foot applied horizontally, simultaneously with a uniform load of 100 pounds per linear foot, applied vertically downward. The concentrated load need not be assumed to act simultaneously with the uniform loads.

Horizontal bars of the infill system shall be capable of withstanding: 1) A concentrated load of 200 pounds applied at any point in any direction; and, 2) A uniform load of 50 pounds per linear foot applied in any direction. The concentrated load need not be assumed to act simultaneously with the uniform load.

Infill areas, consisting of baluster bars, shall be capable of withstanding a horizontal concentrated load of 200 pounds applied to one square foot at any point. This load need not be assumed to act simultaneously with the loads on the top rails in determining stress on the railing system.

COMMON EXCAVATION:

Replace the earthwork table quantities shown on the plans with those below

FILL +20%	1,770	CYS.
COMMON EXCAVATION	1,585	CYS.
BORROW (185 Rdwy + 110 Ditch Lining)	295	CYS.
WET EXCAVATION.....	290	CYS.
BENCHING (ESTIMATED)*	396	CYS.

ITEMIZED PROPOSAL:

Paragraph 4 on page 18 of the special provisions shall be revised as follows:

Herbicide application shall be performed by a person having a Category ~~3~~ **6** certification from the Office of the State Chemist. All chemicals shall be stored, handled, and applied in accordance with the product label. Spraying will not be allowed if the wind is such that the product is carried outside the intended application area.

ITEMIZED PROPOSAL:

Remove existing and insert attached Itemized Proposal (Rev 5/11/16).

**Tippecanoe County Bridge No. 165
Itemized Proposal (Rev 5-11-16)**

ITEM	SPEC CODE	DESCRIPTION	UNIT	QTY	UNIT PRICE	COST
1	105	CONSTRUCTION ENGINEERING	LS	1		
2	110	MOBILIZATION AND DEMOBILIZATION	LS	1		
3	201	CLEARING RIGHT OF WAY	LS	1		
4	202	PRESENT STRUCTURE, REMOVE	LS	1		
5	203	EXCAVATION, COMMON	CYS	1585		
6	203	BORROW	CYS	295		
7	203	TEMPORARY SHORING	LS	1		
8	205	SEDIMENT, REMOVE	CYS	135		
9	205	SPLASH PAD	TONS	3		
10	205	TEMPORARY RIPRAP	TONS	170		
11	205	TEMPORARY MULCH	TONS	3		
12	205	TEMPORARY SILT FENCE	LFT	958		
13	205	TEMPORARY SLOPE DRAIN	LFT	75		
14	205	TEMPORARY NO. 2 STONE	TONS	119		
15	205	TEMPORARY SANDBAGS OR RIPRAP	TONS	98		
16	205	TEMPORARY IMPERVIOUS SHEETING	SYS	228		
17	205	MANUFACTURED SURFACE PROTECTION PRODUCT	SYS	1864		
18	205	TEMPORARY CHECK DAM, TRAVERSABLE	LFT	25		
19	205	TEMPORARY FILTER STONE	TONS	71		
20	205	TEMPORARY GEOTEXTILE	SYS	505		
21	205	TEMPORARY PUMP-AROUND	EACH	1		
22	206	EXCAVATION, WET	CYS	290		
23	207	SUBGRADE TREATMENT, TYPE IC	SYS	1272		
24	207	SUBGRADE TREATMENT, TYPE II	SYS	259		
25	211	STRUCTURE BACKFILL, TYPE 1	CYS	170.4		
26	211	STRUCTURE BACKFILL, TYPE 4	CYS	26.6		
27	211	B-BORROW FOR SUBGRADE IMPROVEMENT	CYS	200		
28	301	COMPACTED AGGREGATE, NO. 53, BASE	TON	861		
29	302	DENSE GRADED SUBBASE	TON	35		
30	303	NO. 2 STONE	TON	96		
31	304	WIDENING WITH HMA, TYPE C	TON	120		
32	306	MILLING, ASPHALT, 1 IN.	SYS	196		
33	306	MILLING, ASPHALT, 1 1/2 IN.	SYS	733		
34	306	MILLING, SCARIFICATION / PROFILE	SYS	196		
35	402	HMA SURFACE, TYPE A	TONS	139		
36	402	HMA SURFACE, TYPE C	TONS	114		
37	402	HMA INTERMEDIATE, TYPE C	TONS	78		
38	402	HMA BASE, TYPE C	TONS	14		
39	402	HMA WEDGE AND LEVEL, TYPE C	TONS	18		
40	406	ASPHALT FOR TACK COAT	TONS	1		
41	601	GUARDRAIL, TRANSITION, TYPE TGB	EACH	4		
42	601	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 5	EACH	1		

**Tippecanoe County Bridge No. 165
Itemized Proposal (Rev 5-11-16)**

ITEM	SPEC CODE	DESCRIPTION	UNIT	QTY	UNIT PRICE	COST
43	601	GUARDRAIL, REMOVE	LFT	851		
44	601	GUARDRAIL END TREATMENT, OS	EACH	3		
45	601	GUARDRAIL, W-BEAM, 6 FT. 3 IN. SPACING	LFT	331.25		
46	602	BARRIER DELINEATOR	EACH	12		
47	604	RAILING, GALVANIZED STEEL PIPE	LFT	325		
48	604	HAND RAIL, GALVANIZED STEEL PIPE	LFT	99		
49	609	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	SYS	207.6		
50	610	HMA FOR APPROACHES, TYPE B	TONS	72		
51	611	MAILBOX ASSEMBLY, SINGLE	EACH	2		
52	611	MAILBOX ASSEMBLY, DOUBLE	EACH	3		
53	615	RIGHT OF WAY MARKER	EACH	1		
54	615	MONUMENT, B	EACH	1		
55	615	BRONZE PLAQUE	EACH	1		
56	616	GEOTEXTILES	SYS	1137		
57	616	REVTMENT RIPRAP	TONS	344		
58	621	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	EACH	2		
59	621	PERMANENT TURF REINFORCEMENT MAT	SYS	94		
60	621	MULCHED SEEDING, R	SYS	706		
61	621	FERTILIZER	TONS	0.25		
62	621	SEED MIXTURE, T	LBS	275		
63	621	MULCHING MATERIAL	TONS	0.1		
64	621	WATER	KGAL	3		
65	621	SODDING, NURSERY	SYS	745		
66	622	PLANT, WOODY RIPARIAN	EACH	300		
67	622	SEEDING, HERBACEOUS RIPARIAN	SYS	5166		
68	622	SIGN, DO NOT MOW OR SPRAY	EACH	5		
69	625	GABIONS, METALLIC COATED	CYS	370		
70	628	FIELD OFFICE, A	MOS	8		
71	701	PILE, STEEL PIPE, 0.312 IN., 14 IN. DIA.	LFT	1980		
72	701	PILE, STEEL PIPE, 0.312 IN., 14 IN. DIA., LOW HEADROOM	LFT	340		
73	701	CONICAL PILE TIP, 14 IN.	EACH	60		
74	701	TEST PILE, DYNAMIC, PRODUCTION	LFT	50		
75	701	DYNAMIC PILE LOAD TEST	EACH	1		
76	701	TEST PILE, DYNAMIC, RESTRIKE	EACH	1		
77	702	CONCRETE, A, SUBSTRUCTURE	CYS	181.5		
78	702	CONCRETE, B, FOOTINGS	CYS	16		
79	702	CONCRETE, CLASS A, STAIRS AND SLAB	CYS	33.4		
80	703	REINFORCING BARS	LBS	71,202		
81	703	REINFORCING BARS, EPOXY COATED	LBS	74,728		
82	704	CONCRETE, C, SUPERSTRUCTURE	CYS	684.5		
83	706	RAILING, BRIDGE, TEMPORARY	LFT	144.8		
84	706	CONCRETE BRIDGE RAILING TRANSITION, TTX	EACH	4		

**Tippecanoe County Bridge No. 165
Itemized Proposal (Rev 5-11-16)**

ITEM	SPEC CODE	DESCRIPTION	UNIT	QTY	UNIT PRICE	COST
85	706	RAILING, CONCRETE, TX	LFT	363		
86	708	WELDED WIRE FABRIC	SYS	114		
87	709	SURFACE SEAL	LS	1		
88	715	PIPE, TYPE 3, CIRCULAR, 30 IN.	LFT	40		
89	715	CONCRETE ANCHOR, MIN. AREA 35 SFT	EACH	1		
90	715	CONCRETE ANCHOR, MIN. AREA 35 SFT, MODIFIED	EACH	1		
91	715	PIPE, TYPE 3, DEFORMED, MIN. AREA 35 SFT	LFT	34		
92	715	PIPE END SECTION, 30 IN.	EACH	1		
93	721	AUTOMATIC DRAINAGE GATE, 30 IN.	EACH	1		
94	801	TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LS	1		
95	801	CONSTRUCTION SIGN, C	EACH	2		
96	801	CONSTRUCTION SIGN, D	EACH	21		
97	801	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	LFT	3900		
98	801	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 8 IN.	LFT	44		
99	801	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	LFT	22		
100	801	CONSTRUCTION SIGN, A	EACH	15		
101	801	CONSTRUCTION SIGN, B	EACH	10		
102	801	MAINTAINING TRAFFIC	LS	1		
103	801	BARRICADE, III-A	LFT	20		
104	801	TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	LFT	480		
105	801	TEMPORARY TRAFFIC BARRIER, TOWER PROTECTION	LFT	60		
106	802	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	SFT	9		
107	802	SIGN POST, A	LFT	46		
108	808	LINE, PAINT, SOLID, WHITE, 5 IN.	LFT	1600		
109	808	LINE, PAINT, SOLID, YELLOW, 5 IN.	LFT	1600		
110	808	LINE, REMOVE	LFT	1190		

TOTAL

Submitted By:

Contractor Name: _____

Authorized Signature: _____

Date: _____

Acknowledgement of Receipt of Addendum No. 1


ADDENDUM No. 2

TIPPECANOE COUNTY BRIDGE No 165

May 12, 2016

INDEX OF CONTENTS

Addendum No. 2 consists of 2 pages
and one 3 page attachment



Stewart W. Kline
P.E. No. 870144

H. STEWART KLINE & ASSOCIATES, INC.
106 South 16th Street
Lafayette, IN 47902
www.HSKline.com

Addendum No. 2

2016 TIPPECANOE COUNTY BRIDGE No 165

TO: ALL BIDDERS

Addendum No. 2, dated May 12, 2016, to the Plans and Specifications for the above noted project as prepared by H. Stewart Kline & Associates, Inc.

This Addendum shall hereby be made a part of the Contract Documents, the same as if originally bound thereto. The following clarifications, amendments, additions, revisions, changes, and/or modifications, change the original Contract Documents only in the manner and to the extent hereinafter specified in the Addendum.

Each Bidder shall acknowledge receipt of the Addendum on his proposal. All bidders should review these items to ascertain whether their Work is affected by the same.

BID OPENING DATE REVISION:

The Bid due date for the project has been extended 1 week. The notice to bidders is revised as follows:

The Board of Commissioners of Tippecanoe County, of the State of Indiana, will receive sealed bids at the office of Bob Plantenga, Auditor of Tippecanoe County and Secretary to the Board of Commissioners, in the Tippecanoe County Office Building, 20 North Third Street, Lafayette, Indiana, on or before 9:30 A.M. on the 46th 23rd day of May, 2016, for the following project:

REPLACEMENT OF TIPPECANOE COUNTY BRIDGE NO. 165, ON BURNETT'S ROAD OVER BURNETT'S CREEK IN TIPPECANOE TOWNSHIP.

THE PROPOSED WORK INCLUDES REMOVAL OF A FIVE-SPAN BRIDGE, CONSTRUCTION OF A 182 FT LONG FOUR-SPAN REINFORCED CONCRETE SLAB BRIDGE, 500 LINEAR FEET OF ASPHALT ROADWAY WIDENING, TRAFFIC MAINTENANCE, GUARDRAIL, GABION WALL, CULVERTS, DRIVE ENTRANCES, RECREATIONAL TRAIL AMENITIES, AND HABITAT REVEGETATION.

Bids will be publicly opened and read aloud at the a special Board of Commissioners meeting in the Tippecanoe Room in the Tippecanoe County Office Building, 20 North Third Street, commencing at 10:00 A.M. on the 46th 23rd day of May, 2016.

Revised notices are attached.

NOTICE TO BIDDERS

(LEGAL NOTICE)

The Board of Commissioners of Tippecanoe County, of the State of Indiana, will receive sealed bids at the office of Bob Plantenga, Auditor of Tippecanoe County and Secretary to the Board of Commissioners, in the Tippecanoe County Office Building, 20 North Third Street, Lafayette, Indiana, on or before **9:30 A.M. on the 23rd day of May, 2016**, for the following project:

REPLACEMENT OF TIPPECANOE COUNTY BRIDGE NO. 165, ON BURNETT'S ROAD OVER BURNETT'S CREEK IN TIPPECANOE TOWNSHIP.

THE PROPOSED WORK INCLUDES REMOVAL OF A FIVE-SPAN BRIDGE, CONSTRUCTION OF A 182 FT LONG FOUR-SPAN REINFORCED CONCRETE SLAB BRIDGE, 500 LINEAR FEET OF ASPHALT ROADWAY WIDENING, TRAFFIC MAINTENANCE, GUARDRAIL, GABION WALL, CULVERTS, DRIVE ENTRANCES, RECREATIONAL TRAIL AMENITIES, AND HABITAT REVEGETATION.

Bids will be publicly opened and read aloud at a **special** Board of Commissioners meeting in the Tippecanoe Room in the Tippecanoe County Office Building, 20 North Third Street, commencing at **10:00 A.M. on the 23rd day of May, 2016**.

More detailed bid requirement information is included in the "Notice to Bidders - Specification Copy" which is a part of the Bid Documents.

Bid Documents may be examined at the following locations: The office of the Tippecanoe County Highway Department, Tippecanoe County Office Building, 20 North Third Street, Lafayette, Indiana; the office of H. Stewart Kline & Associates, Inc., 106 South 16th Street, Lafayette, Indiana; and online at HSKline.com. Documents will be available on or about the **2nd day of May, 2016**. Full-size plan sets (\$15.00) and contract information books (\$10.00) may be purchased at the office of the Tippecanoe County Highway Department or the office of H. Stewart Kline & Associates.

Bids shall be submitted on regular bid forms as prescribed by the State of Indiana. All bids must be accompanied by Bidders Bond, Certified Check or Cash in the amount of Five Percent (5%) of the total bid price, and a non-collusion affidavit, and in all particulars must comply with the laws of the State of Indiana.

Each proposal shall be in a sealed envelope directed to the Board of Commissioners of Tippecanoe County, State of Indiana, and plainly marked to indicate the title of the project and the name and address of the bidder.

The Boards reserve the right to reject any and all bids and to waive, to the extent permitted by law, any of the terms, conditions, or provisions contained in this Notice to Bidders or the Instructions to Bidders, or any informality, irregularity, or omission of any bid provided that such waiver shall, in the discretion of the Boards, be to the advantage of Tippecanoe County.

Tippecanoe County Board of Commissioners

David S. Byers, President

Tracy A. Brown, Vice-President

Thomas P. Murtaugh, Member

Bob Plantenga, Auditor, Secretary to the Board

Dates Advertised: April 29, 2016 and May 6, 2016

NOTICE TO BIDDERS

(SPECIFICATION COPY)

The Tippecanoe County Board of Commissioners of the State of Indiana will receive sealed bids for the following project:

REPLACEMENT OF TIPPECANOE COUNTY BRIDGE NO. 165, ON BURNETT'S ROAD OVER BURNETT'S CREEK IN TIPPECANOE TOWNSHIP.

THE PROPOSED WORK INCLUDES REMOVAL OF A FIVE-SPAN BRIDGE, CONSTRUCTION OF A 182 FT LONG FOUR-SPAN REINFORCED CONCRETE SLAB BRIDGE, 500 LINEAR FEET OF ASPHALT ROADWAY WIDENING, TRAFFIC MAINTENANCE, GUARDRAIL, GABION WALL, CULVERTS, DRIVE ENTRANCES, RECREATIONAL TRAIL AMENITIES, AND HABITAT REVEGETATION.

until the hour of **9:30 A.M. on the 23rd day of May, 2016** at the office of Bob Plantenga, Auditor of Tippecanoe County and Secretary to the Board of Commissioners, in the Tippecanoe County Office Building, 20 North Third Street, Lafayette, Indiana. Bids received after such time will be returned unopened. Bids will be publicly opened and read aloud at a **special** Board of Commissioners meeting in the Tippecanoe Room, commencing at **10:00 A.M.** of the same day.

Bids may be withdrawn prior to the time they are due, but no bids shall be withdrawn for a period of forty five (45) days thereafter.

All documents with each proposal shall be properly executed and addressed to the Board of Commissioners of Tippecanoe County, State of Indiana, c/o the Auditor of Tippecanoe County. The documents to be submitted consist of the following: a) A properly and completely executed Form No. 96 (Revised 2013, as prescribed by the Indiana State Board of Accounts), including Contractor's Financial Statement reflecting conditions not more than four (4) months prior to date of bids, Non-Collusion Affidavit, Experience Questionnaire, and Plan and Equipment Questionnaire; b) Two (2) properly and completely executed copies of the Itemized Proposal Form furnished with the bid documents; and, c) One (1) executed copy of the Contract For Public Work.

EACH PROPOSAL SHALL BE IN A SEALED ENVELOPE DIRECTED TO THE BOARD OF COMMISSIONERS, TIPPECANOE COUNTY, STATE OF INDIANA, AND PLAINLY MARKED TO INDICATE THE TITLE OF THE PROJECT AND THE NAME AND ADDRESS OF THE BIDDER.

EACH BID SHALL BE ACCOMPANIED BY A BID BOND, PROPERLY EXECUTED BY A CORPORATE SURETY COMPANY SATISFACTORY TO THE BOARD AND PAYABLE TO THE BOARD OF COMMISSIONERS OF TIPPECANOE COUNTY. THE BID BOND SHALL BE IN THE PENAL SUM OF FIVE PERCENT (5%) OF THE AMOUNT BID. IT SHALL GUARANTEE THAT THE BIDDER WILL ENTER INTO A CONTRACT, IF HIS BID IS ACCEPTED, AND WILL PERFORM THE OBLIGATIONS SET FORTH IN THE BID.

THE BIDDER WHOSE BID IS ACCEPTED WILL BE REQUIRED TO FURNISH BOTH A PERFORMANCE BOND AND A MAINTENANCE BOND.

THE PERFORMANCE BOND SHALL BE IN THE PENAL SUM OF NOT LESS THAN ONE HUNDRED PERCENT (100%) OF THE AMOUNT BID. IT SHALL BE CONDITIONED ON THE FAITHFUL PERFORMANCE OF THE WORK IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, ON THE PAYMENT BY THE CONTRACTOR AND ALL SUBCONTRACTORS FOR LABOR PERFORMED AND MATERIALS FURNISHED, AND FOR THE PAYMENT, OR THE PERFORMANCE OF, OTHER SERVICES RENDERED IN CONNECTION WITH THE SATISFACTORY COMPLETION OF THE WORK SET OUT IN THE PROPOSAL. THE PERFORMANCE BOND SHALL BE IN FULL FORCE AND EFFECT FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF FINAL ACCEPTANCE OF THE WORK.

THE BIDDERS MAY, AT THEIR OPTION, PROVIDE A COMBINATION BID AND PERFORMANCE BOND WITH THEIR BID. IF THE BIDDER WHOSE BID IS SELECTED ELECTS TO PROVIDE A SEPARATE PERFORMANCE BOND, SUCH BOND SHALL BE DELIVERED TO THE BOARD OF COMMISSIONERS WITHIN TEN (10) DAYS OF THE AWARDING OF THE CONTRACT.

THE MAINTENANCE BOND SHALL BE IN THE PENAL SUM OF NOT LESS THAN ONE HUNDRED PERCENT (100%) OF THE AMOUNT BID. IT SHALL BE CONDITIONED SUCH THAT ALL WORK PERFORMED SHALL BE FREE FROM DEFECTS OF WORKMANSHIP AND MATERIALS FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF SUBSTANTIAL COMPLETION OF THE WORK AND DELIVERED TO THE BOARD OF COMMISSIONERS WITHIN TEN (10) DAYS OF THE AWARDING OF THE CONTRACT.

The Tippecanoe County Board of Commissioners of the State of Indiana reserves the right to waive any informality in bidding and to reject any and all bids.

Bid Documents may be examined at the following locations: The office of the Tippecanoe County Highway Department, Tippecanoe County Office Building, 20 North Third Street, Lafayette, Indiana; the office of H. Stewart Kline & Associates, Inc., 106 South 16th Street, Lafayette, Indiana; and online at HSKline.com. Documents will be available on or about the **2nd day of May, 2016**. Full-size plan sets (\$15.00) and contract information books (\$10.00) may be purchased at the office of the Tippecanoe County Highway Department or the office of H. Stewart Kline & Associates.

Tippecanoe County Board of Commissioners

David S. Byers, President

Tracy A. Brown, Vice-President

Thomas P. Murtaugh, Member

Bob Plantenga, Auditor, Secretary to the Board


ADDENDUM No. 3

TIPPECANOE COUNTY BRIDGE No 165

May 19, 2016

INDEX OF CONTENTS

Addendum No. 2 consists of 2 pages
and one 3 page attachment



Stewart W. Kline
P.E. No. 870144

H. STEWART KLINE & ASSOCIATES, INC.
106 South 16th Street
Lafayette, IN 47902
www.HSKline.com

Addendum No. 3

2016 TIPPECANOE COUNTY BRIDGE No 165

TO: ALL BIDDERS

Addendum No. 2, dated May 12, 2016, to the Plans and Specifications for the above noted project as prepared by H. Stewart Kline & Associates, Inc.

This Addendum shall hereby be made a part of the Contract Documents, the same as if originally bound thereto. The following clarifications, amendments, additions, revisions, changes, and/or modifications, change the original Contract Documents only in the manner and to the extent hereinafter specified in the Addendum.

Each Bidder shall acknowledge receipt of the Addendum on his proposal. All bidders should review these items to ascertain whether their Work is affected by the same.

ITEMIZED PROPOSAL REVISIONS:

Wherever "DENSE GRADED SUBBASE" is shown on the plans or Bid Book, the quantity shall be CY in accordance with Section 302.09.

Item No. 70 Field Office has been deleted from the contract.

The attached Revised Itemized Proposal reflects the above changes.

**Tippecanoe County Bridge No. 165
Itemized Proposal (Rev 5-19-16)**

ITEM	SPEC CODE	DESCRIPTION	UNIT	QTY	UNIT PRICE	COST
1	105	CONSTRUCTION ENGINEERING	LS	1		
2	110	MOBILIZATION AND DEMOBILIZATION	LS	1		
3	201	CLEARING RIGHT OF WAY	LS	1		
4	202	PRESENT STRUCTURE, REMOVE	LS	1		
5	203	EXCAVATION, COMMON	CYS	1585		
6	203	BORROW	CYS	295		
7	203	TEMPORARY SHORING	LS	1		
8	205	SEDIMENT, REMOVE	CYS	135		
9	205	SPLASH PAD	TONS	3		
10	205	TEMPORARY RIPRAP	TONS	170		
11	205	TEMPORARY MULCH	TONS	3		
12	205	TEMPORARY SILT FENCE	LFT	958		
13	205	TEMPORARY SLOPE DRAIN	LFT	75		
14	205	TEMPORARY NO. 2 STONE	TONS	119		
15	205	TEMPORARY SANDBAGS OR RIPRAP	TONS	98		
16	205	TEMPORARY IMPERVIOUS SHEETING	SYS	228		
17	205	MANUFACTURED SURFACE PROTECTION PRODUCT	SYS	1864		
18	205	TEMPORARY CHECK DAM, TRAVERSABLE	LFT	25		
19	205	TEMPORARY FILTER STONE	TONS	71		
20	205	TEMPORARY GEOTEXTILE	SYS	505		
21	205	TEMPORARY PUMP-AROUND	EACH	1		
22	206	EXCAVATION, WET	CYS	290		
23	207	SUBGRADE TREATMENT, TYPE IC	SYS	1272		
24	207	SUBGRADE TREATMENT, TYPE II	SYS	259		
25	211	STRUCTURE BACKFILL, TYPE 1	CYS	170.4		
26	211	STRUCTURE BACKFILL, TYPE 4	CYS	26.6		
27	211	B-BORROW FOR SUBGRADE IMPROVEMENT	CYS	200		
28	301	COMPACTED AGGREGATE, NO. 53, BASE	TON	861		
29	302	DENSE GRADED SUBBASE	CYS	35		
30	303	NO. 2 STONE	TON	96		
31	304	WIDENING WITH HMA, TYPE C	TON	120		
32	306	MILLING, ASPHALT, 1 IN.	SYS	196		
33	306	MILLING, ASPHALT, 1 1/2 IN.	SYS	733		
34	306	MILLING, SCARIFICATION / PROFILE	SYS	196		
35	402	HMA SURFACE, TYPE A	TONS	139		
36	402	HMA SURFACE, TYPE C	TONS	114		
37	402	HMA INTERMEDIATE, TYPE C	TONS	78		
38	402	HMA BASE, TYPE C	TONS	14		
39	402	HMA WEDGE AND LEVEL, TYPE C	TONS	18		
40	406	ASPHALT FOR TACK COAT	TONS	1		
41	601	GUARDRAIL, TRANSITION, TYPE TGB	EACH	4		
42	601	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 5	EACH	1		

**Tippecanoe County Bridge No. 165
Itemized Proposal (Rev 5-19-16)**

ITEM	SPEC CODE	DESCRIPTION	UNIT	QTY	UNIT PRICE	COST
43	601	GUARDRAIL, REMOVE	LFT	851		
44	601	GUARDRAIL END TREATMENT, OS	EACH	3		
45	601	GUARDRAIL, W-BEAM, 6 FT. 3 IN. SPACING	LFT	331.25		
46	602	BARRIER DELINEATOR	EACH	12		
47	604	RAILING, GALVANIZED STEEL PIPE	LFT	325		
48	604	HAND RAIL, GALVANIZED STEEL PIPE	LFT	99		
49	609	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	SYS	207.6		
50	610	HMA FOR APPROACHES, TYPE B	TONS	72		
51	611	MAILBOX ASSEMBLY, SINGLE	EACH	2		
52	611	MAILBOX ASSEMBLY, DOUBLE	EACH	3		
53	615	RIGHT OF WAY MARKER	EACH	1		
54	615	MONUMENT, B	EACH	1		
55	615	BRONZE PLAQUE	EACH	1		
56	616	GEOTEXTILES	SYS	1137		
57	616	REVTMENT RIPRAP	TONS	344		
58	621	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	EACH	2		
59	621	PERMANENT TURF REINFORCEMENT MAT	SYS	94		
60	621	MULCHED SEEDING, R	SYS	706		
61	621	FERTILIZER	TONS	0.25		
62	621	SEED MIXTURE, T	LBS	275		
63	621	MULCHING MATERIAL	TONS	0.1		
64	621	WATER	KGAL	3		
65	621	SODDING, NURSERY	SYS	745		
66	622	PLANT, WOODY RIPARIAN	EACH	300		
67	622	SEEDING, HERBACEOUS RIPARIAN	SYS	5166		
68	622	SIGN, DO NOT MOW OR SPRAY	EACH	5		
69	625	GABIONS, METALLIC COATED	CYS	370		
70	628	FIELD OFFICE, A	MOS	8		
71	701	PILE, STEEL PIPE, 0.312 IN., 14 IN. DIA.	LFT	1980		
72	701	PILE, STEEL PIPE, 0.312 IN., 14 IN. DIA., LOW HEADROOM	LFT	340		
73	701	CONICAL PILE TIP, 14 IN.	EACH	60		
74	701	TEST PILE, DYNAMIC, PRODUCTION	LFT	50		
75	701	DYNAMIC PILE LOAD TEST	EACH	1		
76	701	TEST PILE, DYNAMIC, RESTRIKE	EACH	1		
77	702	CONCRETE, A, SUBSTRUCTURE	CYS	181.5		
78	702	CONCRETE, B, FOOTINGS	CYS	16		
79	702	CONCRETE, CLASS A, STAIRS AND SLAB	CYS	33.4		
80	703	REINFORCING BARS	LBS	71,202		
81	703	REINFORCING BARS, EPOXY COATED	LBS	74,728		
82	704	CONCRETE, C, SUPERSTRUCTURE	CYS	684.5		
83	706	RAILING, BRIDGE, TEMPORARY	LFT	144.8		
84	706	CONCRETE BRIDGE RAILING TRANSITION, TTX	EACH	4		

**Tippecanoe County Bridge No. 165
Itemized Proposal (Rev 5-19-16)**

ITEM	SPEC CODE	DESCRIPTION	UNIT	QTY	UNIT PRICE	COST
85	706	RAILING, CONCRETE, TX	LFT	363		
86	708	WELDED WIRE FABRIC	SYS	114		
87	709	SURFACE SEAL	LS	1		
88	715	PIPE, TYPE 3, CIRCULAR, 30 IN.	LFT	40		
89	715	CONCRETE ANCHOR, MIN. AREA 35 SFT	EACH	1		
90	715	CONCRETE ANCHOR, MIN. AREA 35 SFT, MODIFIED	EACH	1		
91	715	PIPE, TYPE 3, DEFORMED, MIN. AREA 35 SFT	LFT	34		
92	715	PIPE END SECTION, 30 IN.	EACH	1		
93	721	AUTOMATIC DRAINAGE GATE, 30 IN.	EACH	1		
94	801	TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LS	1		
95	801	CONSTRUCTION SIGN, C	EACH	2		
96	801	CONSTRUCTION SIGN, D	EACH	21		
97	801	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	LFT	3900		
98	801	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 8 IN.	LFT	44		
99	801	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	LFT	22		
100	801	CONSTRUCTION SIGN, A	EACH	15		
101	801	CONSTRUCTION SIGN, B	EACH	10		
102	801	MAINTAINING TRAFFIC	LS	1		
103	801	BARRICADE, III-A	LFT	20		
104	801	TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	LFT	480		
105	801	TEMPORARY TRAFFIC BARRIER, TOWER PROTECTION	LFT	60		
106	802	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	SFT	9		
107	802	SIGN POST, A	LFT	46		
108	808	LINE, PAINT, SOLID, WHITE, 5 IN.	LFT	1600		
109	808	LINE, PAINT, SOLID, YELLOW, 5 IN.	LFT	1600		
110	808	LINE, REMOVE	LFT	1190		

TOTAL _____

Submitted By:

Contractor Name: _____

Authorized Signature: _____

Date: _____

Acknowledgement of Receipt of Addendums No. 1, 2, & 3